

SOLAR SURVEILLANCE TRAILER

Complete mobile surveillance solutions capable of operating anywhere, anytime. Designed to meet the rugged demands of construction sites, Caprock's solar trailer has 10 + years of mobile camera system manufacturing. Systems are designed for easy deployment, 24/7 use, advanced analytics, and comes with the highest quality high mega pixel cameras. Each unit can operate autonomous and self-report any technical problems.



REMOTE SITE MANAGEMENT

View your site live from any location, on any device.



PERIMETER WATCH

Monitor specific areas of concern while still maintaining a full field of view.



SITE SECURITY

Live, 24/7, US based, monitoring services available. Alerts sent to you and/or your local law enforcement of suspicious activities.



TIME LAPSE

Document your project from start to finish with photos captured daily through any of our mobile camera systems.



PTZ CAMERAS

Pant, tilt, and zoom cameras allow for remote camera repositioning when cameras need to be relocated.

TRAILER SPECIFICATIONS

- 4 x 3MP PTZ cameras w/ 30x zoom
- 1 x 1080P Fixed Eyeball
- 1,380W solar array
- 2000 Ah of AGM batteries
- Optional backup generator
- 25' mast height
- Cellular 4G LTE router
- Talk down speaker
- Onboard redundant hard drive
- Lockable control housing
- Backup 120V AC battery charger
- Voltage regulator
- Thermostatically controlled cooling fan

OFFSITE CONTROLS

- Router auto ping for cellular stability
- Power cameras on/off
- IR illuminators on/off
- NVR remote on/off
- Strobes on/off
- Analytics device on/off
- Network switch on/off



DIMENSIONS: DEPLOYED / STOWED

- Length: 14'7" / 14'7"
- Width: 11'7" / 6'9"
- Height: 24'6" / 9'4"
- Weight: 4,280 lbs.